KADUR DIVISION.

The 13th February 1897.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Kadur division, up to 15th March 1897, for constructing a new travellers' bangalo at Tarikere. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1898.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Chikmagalur between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer and accompanied by a statement, in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 250 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing a new travellers' bangalo at Tarikere," in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with Superintending Engineer, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

CONSTRUCTING A NEW TRAVELLERS' BANGALO AT TARIKERE.

Items of work.	*Per.*	*Quantity.*
Earthwork excavation	C. yd.	297
Burnt stone in mortar (foundation and basement)	C. ft.	6,123
Rough stone in mud	„	1,712
Burnt brick in mortar (superstructure)	„	6,621
Do in mud (do)	„	4,095
Do in mortar (arch work)	„	618
Do do (coping)	R. ft.	60
Burnt stone slabs	S. ft.	397
Teak wood work	C. ft.	355
Jungle wood work (reserved)	„	130
Roofing with 1st class Mangalore tiles and teak wood reapers, &c., complete.	Sqr.	71·10
Ridge tiles, fixing in mortar including chunam borders	R. ft.	253
Flooring with concrete 6" thick and plaster over it	Sqr.	28·14
Do gravel and cow dung washing	„	6·91
Ventilating tiles	No.	5
Cornice in chunam (inside of halls, capitals and base of pillars)	R. ft.	511
Plastering in chunam	Sqr.	13,080
Do in mud	„	48·67
Pointing in chunam	„	7·40
Whitewashing (as per plastering interior two coats)	„	150·41
Color washing (do exterior do)	„	35·83
Teak wood doors pannelled with four shutters as per details ($4\frac{1}{2}' \times 7\frac{1}{2}'$) including frames, hinges and ring lock, &c., complete.	No.	2
Do double shutters ($4\frac{1}{2}' \times 7\frac{1}{2}'$) do	„	16
Do do ($4' \times 7'$) do	„	4
Do do ($3\frac{1}{2}' \times 6\frac{1}{2}'$) do	„	4
Do windows with iron bars inside glazed and wooden shutters outside ($4' \times 5\frac{1}{2}'$) including frames.	„	14
Do ventilator swing glazed ($3' \times 4\frac{1}{2}'$) including frames	„	4
Jungle wood doors battened including frames ($3' \times 6'$) lock and key, &c., complete.	„	3
Do windows wooden bars and shutters ($2' \times 2\frac{1}{2}'$) including frames	„	2
Do door small ($3' \times 6'$) including frames, &c., as above	„	5
Wood oiling	Sqr.	31·09
Chocolate painting (doors, windows and ventilators)	„	18·80
Teak wood eave boards (ordinary)	R. ft.	182
Tarring jungle wood work	Lump sum.	
Coir matting	Sqr.	20·88